BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38007

APPROVED SCHEDULE - B

BTP/BBMP/E-PMT/15/2019-20, Date: 01.10.2019

Pothole filling in Balaji layout and Bhadrappa layout and surrounding area in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHARAN SAGAR V ( )		
				In Figures		In Words
1	520.88	Scarifying stone metal crust 50 to 100 mm thick with pick axes along with premix carpet / surface dressing and stacking of old serviceable materials by manual means including cost of all labour charges complete as per specification	sqm	74.45	38779.52	Rupees Seventy Four and Forty Five Paise Only
2	104.18	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification No. 406	cum	1757.12	183056.76	Rupees One Thousand Seven Hundred Fifty Seven and Twelve Paise Only
3	520.88	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2	sqm	321.08	167244.15	Rupees Three Hundred Twenty One and Eight Paise Only

Signature of the Contractor

10/02

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

10/02